

SECTION 09 62 63

STAINLESS STEEL WALL BASE- SANI-BASE COVE RISER

iMPERVIUS GLOBAL™

www.imperviusglobal.com 1-800-953-3213 sales@imperviusglobal.com

PART 1 GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General Conditions and Division 1 Specification Sections apply to this Section.

1.02 SUMMARY

- A. This Section includes stainless steel wall base and installation accessories of the following type:
 - 1. Stainless Steel Sani-Base Cove Riser.

1.03 SUBMITTALS

- A. Product Data: Submit manufacturer's product data for each type of Sani-Base Cove Riser specified, including the following:
 - 1. Installation accessories.
 - 2. Installation instructions.
- B. Samples: Submit samples to the Architect for review prior to delivering materials to the site or commencing the work in this Section.
 - 1. Stainless Steel Sani-Base Cove Riser: Submit 3 full size samples, minimum 4 inches in length, of each type of Stainless Steel Sani-Base Cove Riser required with specified finish.
- C. LEED Submittals:
 - 1. Credit MR 4.1 and Credit MR 4.2 – Recycled Content: Product data and certification letter indicating percentages by weight of post-consumer and pre-consumer recycled content for products having recycled content. Include statement indicating costs for each product having recycled content.
 - a. Submit certification of steel process used in the manufacturing of steel items as well as the industry average recycled content per the steel recycling institute.

2. Credit EQ 4.1 – Adhesives and Sealants: Submit documentation including statement of VOC content.

1.04 QUALITY ASSURANCE

- A. Installer Qualifications: Installation of work of this Section shall be by a subcontractor approved by the manufacturer with a minimum of 5 years' experience in similar work or other decorative metal installations having successful in-service performance.

1.05 DELIVERY, STORAGE AND HANDLING

- A. Packing and Shipping: Deliver materials to site in manufacturer's original unopened packaging with labels intact. Protect finished surfaces with removable wrapping or protective plastic film which will not bond when exposed to sunlight.
- B. Storage: Store Stainless Steel Sani-Base Cove Riser in manufacturer's original packaging, off ground and under cover away from direct sunlight, protected from weather, extreme temperature, moisture or other damage.
- C. Handling: Handle materials so that surfaces are protected. Prevent distortion or damage to fabricated pieces.

1.06 PROJECT/SITE CONDITIONS

- A. Environmental Requirements: Areas to receive Stainless Steel Sani-Base Cove Riser shall be enclosed with HVAC in operation and maintaining temperatures within range expected during building occupancy to avoid thermal dimensional change in lengths of material after installation.

1.07 SCHEDULING AND SEQUENCING

- A. Coordination: Coordinate installation of Stainless Steel Sani-Base Cove Riser with associated flooring and wall finishes and adjacent floor and wall finishes.

1.08 MAINTENANCE

- A. Extra Materials: Furnish 8 lineal feet of each type of Stainless Steel Sani-Base Cove Riser specified and 2 preformed corner units of each type specified for Owner's maintenance use.

PART 2 PRODUCTS

2.01 MATERIALS

- A. Stainless Steel Sheet: ASTM A240, Type 304
 - 1. Gauge: 20 gauge.
 - 2. Finish: No. 4 Brushed in accordance with ASTM A480.
- B. Recycled Content: Stainless steel shall have a postconsumer recycled content plus one-half of pre-consumer recycled content of not less than 25 percent.

2.02 MANUFACTURED SANI-BASE COVE RISER

- A. Type 304 Stainless Steel Sani-Base Cove Riser:
 - 1. 6 inch Sani-base: Model SB-093

2.03 INSTALLATION ACCESSORIES

- A. LEED Requirements: Adhesive shall have a VOC content of 50 g/L or less when calculated according to 40CFR 59, Subpart D (EPA Method 24).
- B. Adhesive: Manufacturer's standard VOC compliant polymer adhesive supplied in 3.5 gallon bucket.

2.04 FABRICATION

- A. Stainless Steel Sani-Base Cove Riser shall be factory formed from stainless steel sheet with directional polish grain oriented parallel with length.
 - 1. Edges shall be free of burrs.
 - 2. Standard Length: 8'-0"
 - 3. Fabricate exposed ends with filler to match profile of Sani-Base Cove Riser.
 - 4. Preformed corners shall be 90 degrees, or as otherwise required to suite corner degree indicated on Drawings. Fabricate preformed corners with minimum 4 inch legs.
 - 5. Pre-drill and countersink base for seating of flush fasteners where base is indicated to be installed with fasteners.

PART 3 EXECUTION

A.01 EXAMINATION

- A. Verification of Conditions: Examine sub surfaces to receive Work and report detrimental conditions in writing to Architect. Commencement of Work will be construed as acceptance of sub surfaces.
 - 1. Painted walls shall be dry and thoroughly cured prior to application of Stainless Steel Sani-Base Cove Riser.
 - 2. Perform adhesion test on painted drywall or plaster walls to receive Stainless Steel Sani-Base Cove Riser in accordance with manufacturer's installation instructions to verify proper adhesion.
 - 3. Verify floor areas where Stainless Steel Sani-Base Cove Riser is to be installed are level within 1/8 inch in 10'-0".
- B. Coordination: Coordinate with other work which affects, connects with, or will be concealed by this Work.
 - 1. Coordinate installation of Stainless Steel Sani-Base Cove Riser with application of wall finishes.
 - 2. Where Stainless Steel Sani-Base Cove Riser is installed after application of wall finish, verify application is completed and ready for installation of base.
 - 3. Install Stainless Steel Sani-Base Cove Riser prior to application of finishes installed after installation of Stainless Steel Sani-Base Cove Riser, such as wall tile, Stainless Steel wall sheeting, FRP, etc.

3.02 PREPARATION

- A. Surface Preparation: Surfaces to receive Stainless Steel Sani-Base Cove Riser shall be cleaned to remove all dust, debris, and other contaminants that would interfere with adhesive bond.
- B. Place Stainless Steel Sani-Base Cove Riser in locations/rooms where units will be installed and acclimate to building conditions as specified herein in Project/Site Conditions article for a minimum period of 24 hours prior to installation.

3.03 INSTALLATION

- A. Adhesive Installation: Install Stainless Steel Sani-Base Cove Riser with adhesive in strict accordance with manufacturer's printed installation instructions.
- B. Install Stainless Steel Sani-Base Cove Riser accurately placed in proper location and in proper alignment with adjoining work and applied finishes.
 - 1. Fit field connections accurately together to form hairline joints.
- C. Where necessary to provide secure attachment at corners, end terminations, or where higher abuse is anticipated, supplement adhesive installation with two (2) countersunk #10 stainless steel screws placed in pre-drilled and countersunk holes located within 1 inch of each exposed end or corner. Set screw heads flush in countersunk hole.

3.04 DAMAGE AND REPAIR

- A. Upon completion of the installation, visually check exposed surfaces of the work of this Section, and touch up scratches and damaged surfaces by field polishing so they are completely invisible to the unaided eye from a distance of five feet.

3.05 CLEANING

- A. Upon completion of installation of Stainless Steel Sani-Base Cove Riser, promptly clean exposed surfaces in accordance with recommendations of the Stainless Steel Sani-Base Cove Riser's manufacturer to remove all traces of dust, dirt, adhesive, and other foreign materials.
- B. During the course of the Work and on completion, remove and dispose of excess materials, equipment and debris away from premises. Leave Work in clean condition.

END OF SECTION